United States
Environmental Protection
Agency

Office of Research and Development
Office of Water
Washington, DC 20460

EPA/625/1-91/024
October 1991

Technology Transfer

EPA

Manual

Alternative Wastewater Collection Systems

EPA/625/1-91/024
October 1991

Manual

Alternative Wastewater Collection Systems

U.S. Environmental Protection Agency

Office of Research and Development
Center for Environmental Research Information
Risk Reduction Engineering Laboratory
Cincinnati, Ohio

Office Of Water
Office of Wastewater Enforcement and Compliance
Washington, DC

Printed on Recycled Paper

Notice

This document has been reviewed in accordance with the U.S. Environmental Protection Agency's peer and administrative review policies and approved for publication. Mention of trade names or commercial products does not constitute endorsement or recommendation for use.

Contents

Chapter **Page**

I. OVERVIEW OF ALTERNATIVE CONVEYANCE SYSTEMS

1.1 Introduction 1
1.2 Pressure Systems 3
1.3 Vacuum Systems 7
1.4 Small Diameter Gravity Sewers 22
1.5 Comparison with Conventional Collection 24
1.6 References 25

2 PRESSURE SEWER SYSTEMS

2.1 Introduction 27
2.2 Detailed System Plan and Elevation Views 28
2.3 Detailed Description of On-Lot System Components 30
2.4 System Design Considerations 40
2.5 Construction Considerations 76
2.6 O&M Considerations 79
2.7 System Costs 84
2.8 System Management Considerations 88
2.9 References 90

3 VACUUM SEWER SYSTEMS

3.1 Introduction 93
3.2 System Plan and Elevation Views 95
3.3 Description of System Components 95
3.4 System Design Considerations 102
3.5 Construction Considerations 131
3.6 O&M Considerations 136
3.7 Evaluation of Operating Systems 141
3.8 System Costs 147
3.9 System Management Considerations 153
3.10 References 155

4 SMALL DIAMETER GRAVITY SEWERS

4.1 Introduction 157
4.2 Description of System Components 157
4.3 System Design Considerations 159
4.4 Construction Considerations 172
4.5 O&M Considerations 175
4.6 Review of Operating Systems 181
4.7 System Costs 181
4.8 System management Considerations 191

Contents (continued)

Chapter		Page
4.9	References	191
5	DESIGN EXAMPLES	
5.1	Pressure Sewer System	193
5.2	Vacuum Sewer System	195
5.3	Small Diameter Gravity Sewers	204

Figures

Number		Page
1-1	Installation of pressure sewer main	5
1-2	Grinder Pump (GO) system	6
1-3	Septic Tank Effluent Pump (STEP) system	6
1-4	Liljendahl-Electrolux vacuum system	8
1-5	Vacuum toilet	8
1-6	Colt-Envirovac vacuum system	10
1-7	AIRVAC vacuum system	10
1-8	Major components of a vacuum sewer	13
1-9	AIRVAC valve pit/sump arrangement	14
1-10	Upgrade/downgrade/level transport	15
1-11	Diagram of a typical vacuum station	16
1-12	Early design concept - reformer pockets	18
1-13	Current design concept - pipe bore not sealed	18
1-14	Gravity sewer system example	21
1-15	Vacuum-assisted gravity sewer system example	21
1-16	Schematic of a SDGS system	23
2-1	Piping system appurtenances	29
2-2	Typical simplex GP package using slide away coupling and guide rails	32
2-3	Typical centrifugal GP package with pump suspended from basin cover	33
2-4	Duplex GP station	34
2-5	Typical progressing cavity-type GP package	35
2-6	Basic components of a progressing cavity grinder pump	36
2-7	STEP pump in external vault	37
2-8	Typical STEP package with internal pump vault	38
2-9	Head-discharge curves for typical GP and STEP systems	39
2-10	Wastewater flows for one home	42
2-11	Required pumping rates using flows from Reference 11	42
2-12	Design flows	44
2-13	Zoning of GP or solids handling pump vault	52
2-14	Zoning of a STEP system interceptor tank showing scum and sludge accumulation	55
2-15	Zoning of a STEP system interceptor tank showing liquid levels at pump off, on, and high-level alarm	55
2-16	Two-compartment interceptor tank with hole in baffle wall where clear space expected	57
2-17	Two-compartment interceptor tank using combination tee and 1/4 bend	57
2-18	Multiple-unit interceptor tank and pump assembly	58
2-19	Head-discharge curves for one and multiple centrifugal pumps in parallel	61
2-20	Effective pump curve	62
2-21	Rotor and cutaway stator of progressing cavity-type pump	63
2-22	Typical progressing-cavity pump H-Q curve	64
2-23	Circuit diagram of a basic 120-volt control panel	66
2-24	Wastewater-type air release valve	68
2-25	Basket strainer used with external pump vault	72
2-26	Multi-tray filter, used with external pump vault	72

Figures (continued)

Number		Page
2-27	Outlet tee fitted with well screen	73
2-28	Mesh placed over inlet ports of internal pump vault	73
2-29	Fully-screened internal pump vault	74
2-30	Slotted pump vault	74
2-31	Example lot facility plan	77
3-1	Typical layout - vacuum sewer system	94
3-2	Water sewer/vacuum system similarities	95
3-3	Profile view of typical vacuum sewer line	96
3-4	Plan and profile view - typical valve pit	97
3-5	Auxiliary vent location	99
3-6	Lift detail	99
3-7	Line diagram of a typical vacuum station	100
3-8	Vacuum lift capability	104
3-9	Static loss determination	104
3-10	Top view of crossover connection	108
3-11	Typical configurations for gravity connections	110
3-12	Typical fiberglass valve pit setting	111
3-13	Shallow fiberglass valve pit setting	113
3-14	Plan and elevation views of typical concrete buffer tank	114
3-15	Typical concrete dual buffer tank	115
3-16	Model D arrangement with external breather	117
3-17	Model S arrangement - sump vented	118
3-18	Early system external breather dial	119
3-19	Early system external breather dial	120
3-20	Auxiliary vent detail	121
3-21	AIRVAC cycle counter - two methods of connection	122
3-22	Division valve with gauge tap detail	124
3-23	Terminal access point detail	124
3-24	NPSHa calculation diagram with typical values	127
3-25	Typical elevations of level control probes	130
4-1	Components of a small diameter gravity sewer (SDGS) system	158
4-2	Typical pre-cast concrete interceptor tank	158
4-3	Service lateral installation using a trenching machine	160
4-4	Typical combination cleanout and air release valve detail	160
4-5	Typical STEP lift station detail	161
4-6	Alternative locations for interceptor tanks	165
4-7	Typical interceptor tank outlet baffles	165
4-8	Typical surge chamber detail	166
4-9	Interceptor outlet flow control device	166
4-10a	Typical cleanout detail	168
4-10b	Typical cleanout detail	169
4-11	Ventilated cleanout detail	170
4-12	Australian boundary trap detail	171
4-13	Examples of drop inlets, external and internal	173
4-14	Soil odor filter detail	174
4-15	Example of general easement	176
4-16	Mainline lift station with emergency storage	179
4-17	Emergency pumping manhole	180

Figures (continued)

Number **Page**

5-1 Example pressure sewer design 194
5-2 Design example layout 196
5-3 Design example profiles 197
5-4 Design example profiles 198
5-5 Design example profiles 199
5-6 SDGS design example system profile 205

Tables

Number		Page
1-1	Vacuum Collection System Parameters	11
1-2	Vacuum Station Parameters	11
1-3	Summary of Vacuum System Types	11
1-4	Operating Vacuum Systems in the United States	19
2-1	Approximate Main Sizes Required to Serve Number of Homes Shown	46
2-2	Typical Requirements for Separation of Pressure Sewer Lines from Water Lines	47
2-3	Abbreviated Listing of PVC Pipe Dimensions	49
2-4	Sludge and Scum Accumulation at Glide, Oregon	54
2-5	Typical Zoning Design For a 1,000-gal Interceptor Tank Serving a Single-Family Residence	56
2-6	Distribution of Causes for Call-Out Maintenance On Selected Grinder Pump Pressure Sewer Projects	81
2-7	Distribution of Causes for Call-Out Maintenance On Selected STEP Pressure Sewer Projects	82
2-8	Average Installed Unit Costs (mid-1991) for Pressure Sewer Mains and Appurtenances	85
2-9	Average Installed Unit Costs (mid-1991) for Grinder Pump Services and Appurtenances	85
2-10	Average Unit Costs (mid-1991) for STEP Services and Appurtenances	87
2-11	O&M Cost Accounting Records for the Glide, Oregon Pressure Sewer System	88
3-1	Recommended Lift Height	104
3-2	Main Line Design Parameters	105
3-3	Guidelines for Determining Line Slopes	105
3-4	Governing Distances for Slopes Between Lifts	105
3-5	Maximum Flow for Various Pipe Sizes	105
3-6	Maximum Number of Homes Served for Various Pipe Sizes	105
3-7	Service Line Design Parameters	108
3-8	"A" Factor for Use in Vacuum Pump Sizing	126
3-9	Discharge Pump NPSH Calculation Nomenclature	126
3-10	Values of V_o for a 15-Minute Cycle @ Q_{min} for Different Peaking Factors	127
3-11	Spare Parts List Per Every 50 Valves	132
3-12	Specialty Tools and Equipment for Collection Systems	132
3-13	Specialty Equipment for Vacuum Station	132
3-14	Normal Operating Tasks and Frequencies	138
3-15	Preventive Maintenance Tasks and Frequencies	139
3-16	Operating Systems Visited in 1989	142
3-17	General Information on Operating Systems	143
3-18	Design/Construction Data - Collection System	143
3-19	Design/Construction Data - Vacuum Stations	143
3-20	O&M Data-General Information	144
3-21	O&M Data - Person-Hours/Year	144
3-2	O&M Data - Power Consumption/Year	144
3-23	O&M Data - Mean Time BetweenService Calls	144
3-24	Problem Classification	145
3-25	Average Installed Unit Costs (mid-1990) for Vacuum Sewer Mains and Appurtenances	148

Tables (continued)

Number		Page
3-26	Average Installed Unit Costs (mid-1990) for Vacuum Pits and Appurtenances	148
3-27	Average Installed Cost for Vacuum Station	149
3-28	Typical O&M Cost Components	150
3-29	Person-Hour Estimating Factors	150
3-30	Vacuum Station Power Consumption Estimating Factors	151
3-31	Typical Renewal and Replacement Factors for major Equipment	152
3-32	Annual Budget Example	153
4-1	Summary of SDGS Projects Reviewed	182
4-2	Summary of Interceptor Tank Characteristics Used in Selected projects	184
4-3	Summary of Collector Main Design Criteria Used in Selected projects	185
4-4	Comparison of System Component Use as a Function of Number of Conmnections or Feet of Collection Main Installed in Selected Projects	186
4-5	Comparison of SDGS Construction Costs from Selected Projects	187
4-7	Comparison of Unit Costs of Components from Selected Projects	188
4-7	Summary of Component Costs from Selected Projects	189
4-8	Summary of Component Costs (by percentage) from Selected projects	190
5-1	Design Example Line Loss Calculations	200
5-2	Design Example Line Loss Calculations	201
5-3	Design Example Piping Calculations	202
5-4	Design Example Vacuum Station Calculations	203
5-5	Computations for SDGS Design Example	206

Acknowledgments

Authors:
William C. Bowne, Eugene, OR
Richard C. Naret - Cerrone & Assoc., Wheeling, WV (since 1991 - AIRVAC, Tampa, FL)
Richard J. Otis - Owen Ayres & Associates Inc., Madison, WI 53704

Peer Reviewers:
Paul Farrell - Environment/One, Schenectady, NY
Donald Gray - West Virginia University, Morgantown, WV 26506
Margaret Klepic - Ohio EPA, Columbus, OH
Robert Langford - Airvac, Rochester, IN
Charles Pycha - U.S. EPA Region 5, Chicago, IL
James Wheeler - U.S. EPA-OW, Washington, DC

Technical Direction/Coordination:
James F. Kreissl - U.S. EPA-CERI, Cincinnati, OH
Denis J. Lussier - U.S. EPA-CERI, Cincinnati, OH
Charles P. Vanderlyn - U.S. EPA-OW, Washington, DC

Contract Management:
Arthur J Condren - James M. Montgomery Consulting Engineers, Pasadena CA
Heidi Schultz - Eastern Research Group, Arlington, MA

Extensive review comments were also provided by the Inter-Agency Workgroup on Small Wastewater Systems, whose active membership is:

Denis Lussier
U.S. EPA
Cincinnati, OH

Chuck Pycha
U.S. EPA
Chicago, IL

Brian Yim
U. S. EPA
Seattle, WA

Rao Surampalli
U.S. EPA
Kansas City, KS

Gary Morgan
Farmers Home Administration (FmHA)
Washington, DC 20250

David Kirkman
Department Of Housing and Urban Development (HUD)
Washington, DC

Curtis Townsend
National Park Service (NPS)
Lakewood, CO

Sam Gaddipati
Tennessee Dept. Of Health and Environment
Nashville, TN

Gordon Innes
California State Water Resources Control Board
Sacramento, CA

Randy Orr
NY State Dept. of Environmental Conservation
Albany, NY

George Keller
Maryland Department of The Environment
Baltimore, MD

Fred Reiff
Pan American Health Organization
Washington, DC

Rick Barror
US Public Health Service (IHS)
Rockville, MD

Albert Wright
The World Bank
Washington, DC

Alex Campbell
Ontario Ministry of the Environment
Toronto, Ontario, Canada

Randy Clarkson
Missouri Department of Natural Resources
Jefferson City, MO

Bhupendra Vora
Florida Department of Environmental Regulation
Tallahassee, FL

Margaret Klepic
Ohio EPA
Columbus, OH