# Anaerobic Compost Constructed Wetlands System (CWS) Technology

Innovative Technology Evaluation Report

National Risk Management Research Laboratory Office of Research and Development U.S. Environmental Protection Agency Cincinnati, Ohio 45268

### **Notice**

The information in this document has been funded by the U. S. Environmental Protection Agency (EPA) under Contract No. 68-C5-0037 to Tetra Tech EM Inc. It has been subjected to the Agency's peer and administrative reviews and has been approved for publication as an EPA document. Mention of trade names or commercial products does not constitute an endorsement or recommendation for use.

#### **Foreword**

The U.S. Environmental Protection Agency is charged by Congress with protecting the Nation's land, air, and water resources. Under a mandate of national environmental laws, the Agency strives to formulate and implement actions leading to a compatible balance between human activities and the ability of natural systems to support and nurture life. To meet this mandate, EPA's research program is providing data and technical support for solving environmental problems today and building a science knowledge base necessary to manage our ecological resources wisely, understand how pollutants affect our health, and prevent or reduce environmental risks in the future.

The National Risk Management Research Laboratory is the Agency's center for investigation of technological and management approaches for reducing risks from threats to human health and the environment. The focus of the Laboratory's research program is on methods for the prevention and control of pollution to air, land, water and subsurface resources; protection of water quality in public water systems; remediation of contaminated sites and ground water; and prevention and control of indoor air pollution. The goal of this research effort is to catalyze development and implementation of innovative, cost-effective environmental technologies; develop scientific and engineering information needed by EPA to support regulatory and policy decisions; and provide technical support and information transfer to ensure effective implementation of environmental regulations and strategies.

This publication has been produced as part of the Laboratory's strategic long-term research plan. It is published and made available by EPA's Office of Research and Development to assist the user community and to link researchers with their clients.

Hugh W. McKinnon, Director National Risk Management Research Laboratory

#### **Abstract**

As part of the Superfund Innovative Technology Evaluation (SITE) Program, the U.S. Environmental Protection Agency (EPA) evaluated constructed wetlands systems (CWS) for removing high concentrations of zinc from mine drainage at the Burleigh Tunnel in Silver Plume, Colorado.

Exploration geologists have known for many years that metals, most commonly copper, iron, manganese, uranium, and zinc, frequently accumulate in swamps and bogs located in mineralized areas. This understanding forms the basis for the design of CWS—essentially excavated pits filled with organic matter—that have been developed and constructed over the past 15 years to treat drainage from abandoned coal mines in the eastern United States. Mine drainage is routed through the organic material, where metals are removed through a combination of physical, chemical, and biological processes.

In fall 1994, anaerobic compost wetlands in both upflow and downflow configurations were constructed adjacent to and received drainage from the Burleigh Tunnel, which forms part of the Clear Creek/Central City Superfund site. The systems were operated over a 3-year period. The effectiveness of treatment by the CWS was evaluated by comparing the concentration of zinc and other metals from corresponding influent and effluent analyses. By far the dominant toxic metal present in the drainage was zinc. The upflow CWS removed an average of 93 percent of the zinc during the first year of operation, and 49 and 43 percent during the second and third years. The downflow CWS removed an average of 77 percent of zinc during the first year and 70 percent during the second year. (Flow was discontinued to the downflow system in the third year.)

# Contents

List of Figures and Tables					
Acronyms, Abbreviations, and Symbols					
Con	vers	ion Facto	ors	xi	
Ack	Acknowledgments xii				
Exe	cutiv	e Summ	ary	. 1	
1	Intr	oduction		5	
	1.1	.1 Brief Description of the SITE Program and Reports			
	1.2	.2 Purpose of the Innovative Technology Evaluation Report			
	1.3	Technol	Technology Description		
		1.3.1	Treatment Technology	8	
		1.3.2	System Components and Function	8	
		1.3.3	Key Features of the CWS Technology	9	
	1.4	Key Co	ntacts	11	
2	Tec	Technology Application Analysis			
	2.1	Applica	ble Wastes	12	
	2.2 Factors Affecting Performance			12	
		2.2.1	Mine Drainage Characteristics	12	
		2.2.2	Operating Parameters	13	
		2.2.3	Compost Performance	13	
	2.3	Site Cha	aracteristics	13	
		2.3.1	Support Systems	13	
		2.3.2	Site Area, Preparation, and Access	15	
		2.3.3	Climate	15	
		2.3.4	Utilities	15	
		2.3.5	Services and Supplies	15	
	2.4	4 Availability, Adaptability, and Transportability of Equipment		15	
	2.5	5 Material Handling Requirements		16	
	2.6	Personnel Requirements		16	
	2.7	Potential Community Exposures		16	
	2.8	Evaluation of Technology Against RI/FS Criteria			
	2.9	Potentia	l Regulatory Requirements	18	

# **Contents (continued)**

	2.9.1	Comprehensive Environmental Response, Compensation, and Liability Act	18		
	2.9.2	Resource Conservation and Recovery Act	18		
	2.9.3	Clean Water Act	19		
	2.9.4	Occupational Safety and Health Act	19		
	2.10Limitat	tions of the Technology	19		
3	Treatment I	Effectiveness	22		
	3.1 Backgr	ound	22		
	3.2 Review	of SITE Demonstration	22		
	3.2.1	Treatability Study	22		
	3.2.2	Technology Demonstration	23		
	3.2.3	Operational and Sampling Problems and Variations from the Work Plan	23		
	3.2.4	Site Demobilization	24		
	3.3 Demon	stration Methodology	24		
	3.3.1	Testing Approach	25		
	3.3.2	Sampling, Analysis, and Measurement Procedures	25		
	3.4 Site De	emonstration Results	27		
	3.4.1	Burleigh Mine Drainage Chemistry	27		
	3.4.2	Downflow CWS	27		
	3.4.3	Upflow CWS	36		
	3.4.4	Clear Creek			
	3.4.5	Toxicity Testing Results	40		
	3.4.6	Microbial Toxicity Testing	42		
	3.5 Attainn	nent of Demonstration Objectives	43		
	3.6 Design	Effectiveness	44		
	3.6.1	Downflow Cell	44		
	3.6.2	Upflow Cell	45		
4	Data Qualit	y Review	46		
	4.1 Zinc Data Quality Review				
	4.1.1	Quality Assurance Results for Field Sampling Activities	46		
	4.1.2	Quality Assurance Results for Sample Analysis	47		
	4.2 Acute	Гохісіty Data Quality Review	48		
	4.2.1	Analytical Quality Assurance			
		tical Parameters Data Quality Review			
5		Analysis			
J	ECOHOIIIC A	NII (4) (5) (5) (6) (7) (7) (7) (7) (7) (7) (7) (7) (7) (7	32		

# **Contents (continued)**

	5.1 Basis of	f Economic Analysis			
	5.2 Cost Categories				
	5.2.1	Site Preparation Costs	53		
	5.2.2	Permitting and Regulatory Requirements	53		
	5.2.3	Capital Equipment	53		
	5.2.4	Startup	55		
	5.2.5	Labor	55		
	5.2.6	Consumables and Supplies	55		
	5.2.7	Utilities	55		
	5.2.8	Residual Waste Shipping and Handling	55		
	5.2.9	Analytical Services	55		
	5.2.10	Maintenance and Modifications	55		
	5.2.11	Demobilization	56		
6	Technology	Fechnology Status			
7	References .		58		
Ap	pendix□				
	A Analytical Results Summary Tables				

B Case Study

# **Figures**

1	Site Location	3
2	Schematic Cross-Section of an Anaerobic CWS Upflow Cell	5
3	Flow Rates Measured for Effluent Cells	17
4	CWS Zinc Concentration by Month	21
5	CWS Cadmium Concentration by Month	23
6	CWS Lead Removal by Month	24
7	CWS Manganese Removal by Month	25
8	Sulfate-Reducing Bacteria, Downflow CWS Substrate	27
9	Monthly Zinc Loading, Downflow CWS	29
10	Sulfate-Reducing Bacteria, Upflow CWS Substrate	32
11	Monthly Zinc Loading, Upflow CWS	33
	Tables	
1	Evaluation of CWS Treatment Versus RI/FS Criteria	11
2	Treatment Standards and Influent concentrations for the CWS SITE Demonstration	13
3	Summary of Standard Methods and Procedures	20
4	Average Downflow CWS Substrate Results	26
5	Average Upflow CWS Substrate Results	31
6	Clear Creek Upstream	35
7	Clear Creek Downstream	35
8	CWS Demonstration Toxicity (LC <sub>50</sub> ) Results	36
9	CWS Costs for Different Treatment Flow Rates	47

### Acronyms, Abbreviations, and Symbols

°C Degrees Celsius
°F Degrees Fahrenheit
%C Percent completeness
%R Percent recovery
AA Atomic absorption

ARAR Applicable or relevant and appropriate requirement

ASTM American Society for Testing and Materials

AVS Acid volatile sulfide

BOD Biochemical oxygen demand

CDPHE Colorado Department of Public Health and Environment

CDM Camp, Dresser, & McKee, Inc.

CFU Colony forming units

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR Code of Federal Regulations
CWS Constructed wetlands system

DQO Data quality objective

Eh Oxidation reduction potential

EPA U.S. Environmental Protection Agency

FS Feasibility study
gpm Gallons per minute
H<sub>2</sub>S Hydrogen sulfide

HDPE High-density polyethylene

HSWA Hazardous and Solid Waste Amendments of 1984

ICP Inductively coupled plasma

ITER Innovative technology evaluation report

LC<sub>50</sub> Lethal concentration for 50 percent of the test organisms

MCAWW Methods for Chemical Analysis of Water and Wastes

MCL Maximum contaminant level

μg Micrograms

# Acronyms, Abbreviations, and Symbols (continued)

μS Microsiemens

mg/kg Milligrams per kilogram mg/L Milligrams per liter

MS Matrix spike

NCP National Oil and Hazardous Substances Pollution Contingency Plan

NIST National Institute of Standards and Technology
NPDES National Pollutant Discharge Elimination System
NRMRL National Risk Management Research Laboratory

O&M Operation and maintenance

ORD Office of Research and Development

ORP Oxidation/reduction potential

OSHA Occupational Safety and Health Administration
OSWER Office of Solid Waste and Emergency Response

PPE Personal protective equipment

ppm Parts per million

PRC PRC Environmental Management, Inc.

PVC Polyvinyl chloride

QAPP Quality assurance project plan
QA/QC Quality assurance/quality control

RCRA Resource Conservation and Recovery Act

RI Remedial investigation
RPD Relative percent difference

SARA Superfund Amendments and Reauthorization Act
SITE Superfund Innovative Technology Evaluation

SDWA Safe Drinking Water Act
SOP Standard operating procedure
SRM Standard reference material
SWDA Solid Waste Disposal Act

TCLP Toxicity characteristic leaching procedure

TOC Total organic carbon
TDS Total dissolved solids
TSS Total suspended solids

yd³ Cubic yards

### **Conversion Factors**

$T_{i}$	o Convert From	То	Multiply By
Length	inch foot mile	centimeter meter kilometer	2.54 0.305 1.61
Area:	square foot acre	square meter square meter	0.0929 4,047
Volume:	gallon cubic foot	liter cubic meter	3.78 0.0283
Mass:	pound	kilogram	0.454
Energy:	kilowatt-hour	megajoule	3.60
Power:	kilowatt	horsepower	1.34
Temperature:	(°Fahrenheit - 32)	°Celsius	0.556

#### **Acknowledgments**

This report was prepared under the direction of Mr. Edward Bates, the U.S. Environmental Protection Agency (EPA) Superfund Innovative Technology Evaluation (SITE) project manager at the National Risk Management Research Laboratory (NRMRL) in Cincinnati, Ohio; Ms. Dana Allen, U.S. EPA Region VIII; and Mr. James Lewis, Colorado Department of Public Health and Environment. This report was prepared by Mr. Gary Miller, Mr. Garry Farmer, Mr. Jon Bridges, and Ms. Shaleigh Whitesell of Tetra Tech EM Inc. (Tetra Tech) and Mr. Mark Kadnuck of the Colorado Department of Public Health and Environment (formerly of Tetra Tech). This report was typed by Ms. Robin Richey and Ms. June Diller, edited by Mr. Butch Fries, and reviewed by Dr. Kenneth Partymiller of Tetra Tech.

This project consisted of a demonstration conducted under the SITE program to evaluate the anaerobic compost Constructed Wetland System (CWS) technology developed by the Colorado Department of Public Health and Environment (CDPHE). The technology demonstration was conducted on mineral mine drainage at the Burleigh Tunnel in Silver Plume, Colorado, which is included in the Clear Creek/Central City Superfund site. Passive treatment was selected as the preferred treatment alternative for the Burleigh Tunnel drainage in a 1991 Record of Decision (ROD). This Innovative Technology Evaluation Report (ITER) interprets the data that was collected during the nearly four-year demonstration and discusses the potential applicability of the technology.

The cooperation and participation of the following people are gratefully acknowledged: Mr. Vincent Gallardo, Ms. Ann Vega, and Dr. James Lazorchek of NRMRL; Ms. Holly Fliniau of EPA Region VIII and Mr. Rick Brown of CDPHE.